arXiv:1201.3390v1 [math.OC] 16 Jan 2012

Controllability of the heat equation with an inverse-square potential localized on the boundary

Cristian Cazacu[1] [2]

Abstract

This article is devoted to analyze control properties for the heat equation with singular potential $-\mu/|x|^2$ arising at the boundary of a smooth domain $\Omega \subset \mathbb{R}^N$, $N \geq 1$. This problem was firstly studied by Vancostenoble and Zuazua [18] and then generalized by Ervedoza [8] in the context of interior singularity. Roughly speaking, these results showed that for any value of parameters $\mu \leq \mu(N) := (N-2)^2/4$, the corresponding parabolic system can be controlled to zero with the control distributed in any open subset of the domain. The critical value $\mu(N)$ stands for the best constant in the Hardy inequality with interior singularity.

When considering the case of boundary singularity a better critical Hardy constant is obtained, namely $\mu_N := N^2/4$.

In this article we extend the previous results in [18], [8], to the case of boundary singularity. More precisely, we show that for any $\mu \leq \mu_N$, we can lead the system to zero state using a distributed control in any open subset, excepting some cases where Ω changes the convexity at origin, in which cases the control is distributed in a semi-annulus surrounding the singularity.

We emphasize that our results cannot be obtained straightforwardly from the previous works [18], [8].

Contents

1 Introduction **1**

2 Null controllability in the case $\mu \leq N^2/4$ **6**

2.1 Carleman estimates. A choice of a proper weight σ 6

2.2 Main result 7

2.3 Preliminaries and useful lemmas 8

3 Proofs of technical lemmas **10**

4 Sketch of the proof of Theorem 1.2 **19**

1 Introduction

In this article we present some new results concerning the exact controllability of the heat equation with singular quadratic potential $-\mu/|x|^2$.

From the mathematical viewpoint, the study of problems with inverse-square potentials is motivated by models which appear for instance in the context of combustion theory [15] and quantum mechanics [7].

Evolution problems with the potential $-\mu/|x|^2$ have been intensively studied in the recent decades. Among them, we remind the pionerring work by Baras and Goldstein [2] in which they considered the corresponding heat-like equation with the singularity localized in the interior of a smooth domain $\Omega \subset \mathbb{R}^N$, $N \geq 2$ (If $N = 1$ they deleted the origin so that $0 \in \partial\Omega$, where $\partial\Omega$ denotes the boundary of Ω). They derived necessary and sufficient conditions for such systems

---

[1] BCAM Basque Center for Applied Mathematics, Mazarredo, 14 E-48009 Bilbao - Basque Country - Spain

[2] Departamento de Matemáticas, Universidad Autónoma de Madrid, 28049 Madrid, Spain

to being well-posed. More precisely, they showed the well-posedness holds true whenever $\mu \leq (N-2)^2/4$, whereas if $\mu > (N-2)^2/4$ there is instantaneously blow-up for the solution. The critical value $(N-2)^2/4$ is the best constant in the corresponding Hardy inequality (see e.g. [14], [13]). Later on, the issue of singular or degenerated potentials has been also analyzed by the control community. The authors in [19] analyzed the control and stabilization properties of the corresponding wave equation. Then they showed in Vancostenoble and Zuazua [18] that the corresponding heat equation can be controlled by a distributed control which sourrounds the singularity. This result has been generalized in Ervedoza [8] where any geometrical constraint of the control region was removed. We also mention the paper [3] and references there in studying the control of parabolic equations degenerating at origin. Recently, the work [8] has been slightly improved in [17] when studying some applications to inverse problems. In all situations above the authors showed that the well-posedness, control and stabilization are very much related to the classical Hardy inequality in which the best constant is $(N-2)^2/4$.

In this paper we consider the heat equation with the potential $-\mu/|x|^2$, where the singularity $x=0$ is located on the boundary $\partial\Omega$ of a smooth open set $\Omega \subset \mathbb{R}^N$, $N \geq 1$. This work is aimed to extend to the case of boundary singularity the paper [8] which provides the most general control results in the case when the singularity is localized in the interior of the domain.

We point out that our results cannot be deduced straightforwardly from the case of interior singularity and requires an independent analysis. Our main tools concern in the Carleman estimates which is the classical way to prove observability properties for parabolic systems. The major difficulty consists in finding proper weight functions to develop efficient Carleman estimates. In our case, the weights in [8], [18], are not even allowed to recover the results in the range of parameters $\mu \leq (N-2)^2/4$ shown in the case of interior singularity. A proper modification of the weights in [8], will be done here.

Before entering into details, let us fix some ideas.

Let $N \geq 2$ and consider a smooth bounded domain $\Omega \subset \mathbb{R}^N$ such that $0 \in \partial\Omega$, and let $\omega \subset \Omega$ be a non-empty open set. Assume also that $T > 0$ is fixed. We are interested in the question of controllability of the following problem

$$\begin{cases} \partial_t u - \Delta u - \dfrac{\mu}{|x|^2} u = f, & (x,t) \in \Omega \times (0,T), \\ u(x,t) = 0, & (x,t) \in \partial\Omega \times (0,T), \\ u(x,0) = u_0(x), & x \in \Omega, \end{cases} \tag{1.1}$$

where $u_0 \in L^2(\Omega)$ and $f \in L^2(\Omega \times (0,T))$ is a function supported in the control region ω.

The null-controllability problem reads as follows: Given any $u_0 \in L^2(\Omega)$, find a function $f \in L^2(\omega \times (0,T))$ such that the solution of (1.1) satisfies

$$u(x,T) = 0, \qquad x \in \Omega. \tag{1.2}$$

In order to discuss the well-posedness and null-controllability of (1.1) we need to establish the proper functional framework which corresponds to the problem. The crucial role of this issue is played by a new critical value of μ which determines the features of system (1.1). More precisely, when moving the singularity from interior to the boundary, the critical Hardy constant jumps from $(N-2)^2/4$ to the critical value

$$\mu_N := \frac{N^2}{4}. \tag{1.3}$$

This is guaranteed by the new Hardy inequality with boundary singularities (see e.g. [6], [10], [9]) stated in a simplified form as follows. For any $\mu \leq N^2/4$ there exists a constant $C_1(\gamma, \Omega)$, such that for any $0 < \gamma < 2$ the inequality

$$\int_\Omega \frac{u^2}{|x|^\gamma}\, \mathrm{dx} + \mu \int_\Omega \frac{u^2}{|x|^2}\, \mathrm{dx} \leq \int_\Omega |\nabla u|^2 + C_1(\gamma, \Omega) \int_\Omega u^2\, \mathrm{dx}, \tag{1.4}$$

holds for all $u \in H_0^1(\Omega)$.

Moreover, an improved Hardy inequality (cf. Theorem 1.2, [4]) states that for any $0 < \gamma < 2$ and any $\mu \leq \mu_N = N^2/4$ there exist $C_1(\gamma, \Omega)$, $C_2(\gamma, \Omega) > 0$ such that

$$C_1 \int_\Omega u^2 dx + \int_\Omega \Big[|\nabla u|^2 - \mu \frac{u^2}{|x|^2} \Big] dx \geq C_2 \int_\Omega \Big[|x|^{2-\gamma} |\nabla u|^2 + \frac{u^2}{|x|^\gamma} \Big] dx, \quad \forall u \in H_0^1(\Omega). \tag{1.5}$$

This inequality will be used in the proof of the Carleman estimates.

The main results of this paper are very much related to the geometry of Ω at the origin. In view of that, we say that Ω satisfies the property (P) if

$$(P): \left\{ \begin{array}{c} \text{There exists a neighborhood } \mathcal{V}_0 \text{ of the origin } x = 0 \text{ such that} \\ x \cdot \vec{n} \leq 0, \quad \forall\, x \in \partial\Omega \cap \mathcal{V}_0, \\ \text{where } \vec{n} \text{ denotes the outward normal vector.} \end{array} \right. \tag{1.6}$$

Roughly speaking, a domain $\Omega \subset \mathbb{R}^2$ with the property (P) is either concave or flat in a small neighborhood of the origin, as shown in the cases C1 and C2 in Figure 1.



Figure 1: The geometry of $\Omega \subset \mathbb{R}^2$ is drawn in red color.

Otherwise, a domain $\Omega \subset \mathbb{R}^2$ not verifying the property (P) corresponds to Figure 2 below.



Figure 2: The geometry of $\Omega \subset \mathbb{R}^2$ is drawn in red color.

A domain $\Omega \subset \mathbb{R}^N$ with $N \geq 3$ satisfying the property (P), is much more complicated to be drawn. However, in this multidimensional case, the property (P) may be described through the second fundamental form corresponding to $\partial\Omega$ in a neighborhood of origin (see e.g. [12]). Generally speaking, the property (P) is related to the non-convexity at origin. In particular, a domain strictly convex at origin does not satisfy the property (P).

Next, we are in conditions to state the main results of this paper.

Theorem 1.1 (Null-Controllability)**.** *Let $\Omega \subset \mathbb{R}^N$, $N \geq 1$, be a smooth domain satisfying the property (P) and assume $\mu \leq \mu_N$. Given any non-empty open set $\omega \subset \Omega$, for any time $T > 0$ and any initial data $u_0 \in L^2(\Omega)$, there exists a control $f \in L^2(\omega \times (0,T))$ such that the solution of* (1.1) *satisfies* (1.2).

Theorem 1.2 (Null-Controllability)**.** *Let $\Omega \subset \mathbb{R}^N$, $N \geq 1$, be a smooth domain which does not fulfill the property (P). We also assume $\mu \leq \mu_N$ and let $r_1 > 0$ be a fixed constant.*

Then there exists $r_0 = r_0(\Omega) > 0$ (independent of r_1), $0 < r_0 < r_1$, such that for any time $T > 0$ and any initial data $u_0 \in L^2(\Omega)$, there exists a control $f \in L^2(\omega \times (0,T))$ distributed in the non-empty open set $\omega \subset \Omega$, defined by

$$\omega := \{x \in \Omega \mid r_0 < |x| < r_1\}, \tag{1.7}$$

such that the solution of (1.1) *satisfies* (1.2).

Following the by now classical HUM method (cf. [?]), the controllability property is equivalent to an observability inequality for the adjoint system

$$\begin{cases} \partial_t w + \Delta w + \dfrac{\mu}{|x|^2} w = 0, & (x,t) \in \Omega \times (0,T), \\ w(x,t) = 0, & (x,t) \in \partial\Omega \times (0,T), \\ w(x,T) = w_T(x), & x \in \Omega. \end{cases} \tag{1.8}$$

More precisely, when $\mu \leq \mu_N$, we need to prove that there exists a constant C such that for all $w_T \in L^2(\Omega)$, the solution of (1.8) satisfies

$$\int\limits_{\Omega} |w(x,0)|^2 \text{ dx} \leq C \iint\limits_{\omega \times (0,T)} |w(x,t)|^2 \text{ dx dt}. \tag{1.9}$$

In order to prove (1.9), we will use a particular Carleman estimate , which is by now a classical technique in control theory.Indeed, the Carleman estimate we will derive later implies that for any solution w of (1.8),

$$\iint\limits_{\Omega \times (\frac{T}{4}, \frac{3T}{4})} |w(x,t)|^2 \text{ dx dt} \leq C_T \iint\limits_{\omega \times (0,T)} |w(x,t)|^2 \text{ dx dt}. \tag{1.10}$$

Let us show that (1.10) implies (1.9). Indeed, multiplying the system (1.8) by w and integrating in Ω we formally obtain

$$\frac{1}{2} \frac{d}{\text{dt}} \int_\Omega w^2(x,t) \text{ dx} = \int_\Omega |\nabla w|^2 \text{ dx} - \mu \int_\Omega \frac{w^2}{|x|^2} \text{ dx}.$$

From (1.4) we have that

$$\frac{1}{2} \frac{d}{\text{dt}} \int_\Omega w^2(x,t) \text{ dx} \geq -C_1(\gamma,\Omega) \int_\Omega w^2(x,t) \text{ dx},$$

Then we get that the function $t \mapsto \exp^{2C_1(\gamma,\Omega)t} ||w(\cdot,x)||^2_{L^2(\Omega)}$ is increasing. Then we obtain

$$\int_{T/4}^{3T/4} \int_\Omega w^2(x,t) \text{ dx dt} \geq \frac{T}{2} \exp^{-3TC_1(\gamma,\Omega)/2} \int_\Omega w^2(x,0) \text{ dx}, \tag{1.11}$$

From here and (1.10) we obtain (1.9).

Well-posedness via Hardy inequality

Let us now define the set

$$\mathcal{C} := \Big\{ C \geq 0 \ \text{ s. t. } \quad \inf_{u \in H_0^1(\Omega)} \frac{\int_\Omega \left[|\nabla u|^2 - \mu_N u^2/|x|^2 + C u^2 \right] dx}{\int_\Omega u^2/|x|^\gamma dx} \geq 1 \ \Big\}. \tag{1.12}$$

Of course, $\mathcal{C}$ is non empty due to inequality (1.4). Next we define

$$\mathcal{C}_0 = \inf_{C \in \mathcal{C}} C. \tag{1.13}$$

Then, for any $\mu \leq \mu_N := N^2/4$ we introduce the Hardy functional

$$B_\mu[u] := \int_\Omega |\nabla u|^2 dx - \mu \int_\Omega \frac{u^2}{|x|^2} dx + \mathcal{C}_0 \int_\Omega u^2 dx, \tag{1.14}$$

which is positive for any test function due to inequality (1.4) and the election of $\mathcal{C}_0$. Then we define the corresponding Hilbert space H_μ as the closure of $C_0^\infty(\Omega)$ in the norm induced by $B_\mu[\cdot]$. Observe that for any $\mu < \mu_N$ the identification $H_\mu = H_0^1(\Omega)$ holds true. Indeed, if $\mu < \mu_N$ firstly we have

$$||u||_{H_\mu}^2 \geq \big(1 - \frac{\mu}{\mu_N}\big) \int_\Omega |\nabla u|^2 dx - \frac{\mathcal{C}_0 \mu}{\mu_N} \int_\Omega u^2 dx. \tag{1.15}$$

On the other hand, from the definition of $\mathcal{C}_0$ we obtain that there is a constant $C > 0$ such that

$$||u||_{H_\mu}^2 \geq C \int_\Omega u^2 dx. \tag{1.16}$$

Multiplying (1.16) by $\mathcal{C}_0 \mu/(C_1 \mu_N)$ and summing to (1.15) we get that

$$||u||_{H_\mu}^2 \geq C_\mu \int_\Omega |\nabla u|^2 dx,$$

for some positive constant C_μ (C_μ tends to zero infinity as μ tends to zero).

Besides, in the critical case $\mu = \mu_N$, H_μ is slightly larger than $H_0^1(\Omega)$. However, using cut-off arguments near the singularity (see e.g. [**?**]) we can show that

$$||u||_{H_{\mu(N)}} \geq C_\varepsilon ||u||_{H^1(\Omega \setminus \overline{B_\varepsilon(0)})}, \quad \forall\ u \in H_\mu, \tag{1.17}$$

where C_ε is a constant going to zero as ε tends to zero and $\overline{B_\varepsilon(0)}$ denotes the closure of the ball of radius ε centered at the origin.

Let us define now the operator $A_\mu := -\Delta - \mu/|x|^2 + \mathcal{C}_0 I$ together with its domain as

$$D(A_\mu) := \{ u \in H_\mu \mid A_\mu u \in L^2(\Omega) \}. \tag{1.18}$$

The norm of this operator is given by

$$||u||_{D(A_\mu)} = ||u||_{L^2(\Omega)} + ||A_\mu u||_{L^2(\Omega)} \quad \forall \mu \leq \mu_N. \tag{1.19}$$

With these definitions, by standard semigroup-theory one can show that for any $\mu \leq \mu_N$ the operator $(A_\mu, D(A_\mu))$ generates an analytic semigroup in the pivot space $L^2(\Omega)$ for the equation (1.1). For more details we refer to Theorem II.1, p. 3, [17], which can be adapted in the context of the space H_μ introduced above.

2 Null controllability in the case $\mu \leq N^2/4$

First of all, to simplify the presentation, we assume that $0 \notin \bar{\omega}$ otherwise it is straightforward since the control acts locally near the singularity. We also assume that $\Omega \cap \overline{B_1(0)}$ is included in Ω and $\overline{B_1(0)} \cap \bar{\omega}$ is empty. This can always be done by a scaling argument. In the sequel we also consider a nonempty subset $w_0 \subset\subset w$ whose role will be emphasized in the next paragraph.

In what follows we are going to justify the result of Theorem 1.1. For that we will apply Carleman estimates using a modified Fursikov-Imanuvilov [11] weight ψ which, in particular, satisfies

$$\nabla\psi \cdot x \geq 0, \quad \forall x \in \Omega \cap \mathcal{V}_0, \tag{2.1}$$

in a small neighborhood $\mathcal{V}_0$ of the origin.

In view of that, in the sequel we assume that the geometry of Ω satisfies the property (P). Without losing the generality, by a scaling argument we may assume that the property (P) reduces after normalization to

$$x \cdot \vec{n} \leq 0, \ \forall\ x \in \partial\Omega, \ |x| \leq 1, \tag{2.2}$$

2.1 Carleman estimates. A choice of a proper weight σ

As said in the introduction, the main tool we use to address the observability inequality (1.10) is a Carleman estimate.

The major problem when designing a Carleman estimate is the choice of a smooth weight function σ, which is in general assumed to be positive, and to blow up as t goes to zero and as t goes to T. Hence we are looking for a weight function σ that satisfies:

$$\begin{cases} \sigma(t,x) > 0, \quad (x,t) \in \Omega \times (0,T), \\ \lim\limits_{t\to 0^+} \sigma(t,x) = \lim\limits_{t\to T^-} \sigma(t,x) = +\infty, \quad x \in \Omega. \end{cases} \tag{2.3}$$

When shifting the singularity from interior up to the boundary the weight in Ervedoza [8] violates some necessary conditions to apply the Carleman estimates; the weight ψ blows up at origin and this violates the fact that ψ is constant on the boundary.

In view of that, we propose the weight

$$\sigma(t,x) = \theta(t)\Big(C_\lambda - |x|^2\psi - \big(\frac{|x|}{r_0}\big)^\lambda \phi\Big), \quad \phi := e^{\lambda\psi(x)}, \tag{2.4}$$

where λ is a positive parameter aimed at being large and r_0 is a positive constant aimed to be small enough such that it verifies

$$r_0 \leq \min\Big\{\frac{1}{100}, \frac{1}{2-\gamma}\Big\} \min\Big\{\frac{1}{|D\psi|_{L^\infty(\Omega)} + |D^2\psi|_{L^\infty(\Omega)}}, \\ \Big(\frac{C_2}{8|D\psi|^2_{L^\infty(\Omega)} + 8|D^2\psi|^2_{L^\infty(\Omega)}}\Big)^{1/(\gamma-1)}, \Big(\frac{C_2}{2|\mu||D\psi|_{L^\infty(\Omega)}}\Big)^{1/(\gamma-1)}\Big\} \tag{2.5}$$

where γ is a fixed constant such that $1 < \gamma < 2$, C_2 stands for the constant in inequality (1.5), C_λ is big enough meant to assure the positivity of σ. Besides, ψ and θ are defined as follows. Firstly, we define θ by

$$\theta(t) = \Big(\frac{1}{t(T-t)}\Big)^k, \tag{2.6}$$

with $k = 1 + 2/\gamma$. Next we introduce ψ satisfying the conditions

$$\begin{cases} \psi > 1, & \forall\ x \in \Omega, \\ \psi \equiv 1, & \forall\ x \in \partial\Omega, \\ |\nabla\psi| \geq 2C_\Omega & \forall\ x \in \Omega \setminus \omega_0, \end{cases} \tag{2.7}$$

where the constant $C_\Omega > 0$ in (2.7) is such that verifies

$$|x \cdot \vec{n}| \leq C_\Omega |x|^2, \quad \forall\, x \in \partial\Omega. \tag{2.8}$$

Moreover, we assume that

$$x \cdot \nabla\psi \geq 0, \quad \forall\, x \in \Omega,\ |x| \leq 1. \tag{2.9}$$

Remark 2.1. Such a function ψ satisfying conditions (2.7)-(2.9) exists. Indeed, let us assume $\tilde{\psi}$ is a smooth modification of by now the classical Fursikov-Imanuvilov weight (see [11]), with the following property close to the origin:

$$\tilde{\psi} = d(x) > 0, \quad \forall\, x \in \Omega,\ |x| \leq 1, \tag{2.10}$$

where $d(x) = d(x, \partial\Omega)$ denotes the distance to the boundary. We remark that the distance d yields the conditions (2.7) since it satisfies the eikonal equation $|\nabla d(x)| = 1$ a.e. In particular, the assumptions (2.2)-(2.10) (see e.g. [1]) ensure the validity of (2.9).

To end up, we can choose $\psi := \delta(\tilde{\psi} + 1)$ which satisfies the constraints (2.7)-(2.8) for δ large enough.

Motivation for the choice of the weight σ.

Roughly speaking, in order to show the Carleman estimates below, the weight σ needs to fulfill some necessary conditions:

C1. $\nabla\sigma \cdot \vec{n} \geq 0$, for all $x \in \partial\Omega$.

C2. $-D^2\sigma(x)(\xi, \xi) > 0$, for all $\xi \in \mathbb{R}^N$, $x \in \Omega$, $|x| \leq r_0$, where r_0 is some positive constant independent of λ.

C3. $-\Delta\sigma > 0$, for all $|x| \geq r_0$, $x \notin \omega_0$, where r_0 is the same constant chosen in the condition C2.

C4. In order to get an expression in terms of the optimal Hardy inequality, the gradient term $\nabla\sigma$ must degenerate at origin at least as $|x|$.

The weight $\sigma = C_\lambda - |x|^2\psi - |x|^\lambda e^{\lambda\psi}$ fulfills the conditions C1, C2, C4. Moreover, it verifies the condition C3 provided

$$x \cdot \nabla\psi \geq 0, \quad \forall\, x \in \Omega \cap \mathcal{V}_0 \tag{2.11}$$

for some neighborhood $\mathcal{V}_0$ of the origin. The normalization by r_0 in (2.4) is required by technical reasons needed precisely in the proof of Lemma 2.6.

2.2 Main result

We claim that

Theorem 2.2. *There exists a positive constant K_1 and λ_0 such that for $\lambda \geq \lambda_0$ there exists $s_0(\lambda)$ such that for any $s \geq s_0$ we have*

$$\begin{aligned} s\lambda^2 \iint\limits_{\mathcal{O}\times(0,T)} \theta\Big(\frac{|x|}{r_0}\Big)^{\lambda} \phi e^{-2s\sigma} |\nabla w|^2 \text{ dx dt} + s \iint\limits_{\Omega\times(0,T)} \theta e^{-2s\sigma} \Big[|x|^{2-\gamma}|\nabla w|^2 + \frac{w^2}{|x|^\gamma}\Big] \text{ dx dt} \\ + s^3 \iint\limits_{\Omega\times(0,T)} \theta^3 e^{-2s\sigma}|x|^2|w|^2 \text{ dx dt} + s^3\lambda^4 \iint\limits_{\mathcal{O}\times(0,T)} \theta^3 e^{-2s\sigma}\Big(\frac{|x|}{r_0}\Big)^{3\lambda}\phi^3|w|^2 \text{ dx dt} \\ \leq K\Big(s\lambda^2 \iint\limits_{\omega_0\times(0,T)} \theta\Big(\frac{|x|}{r_0}\Big)^{\lambda}\phi e^{-2s\sigma}|\nabla w|^2 \text{ dx dt} + s^3\lambda^4 \iint\limits_{\omega_0\times(0,T)} \theta^3\Big(\frac{|x|}{r_0}\Big)^{3\lambda}\phi^3 e^{-2s\sigma}|w|^2 \text{ dx dt}\Big). \end{aligned} \tag{2.12}$$

From Theorem 2.2 we can easily obtain the observability inequality (1.9) via Caccioppoli's inequality. The details could be reproduced step by step as in Section 2.2, p. 12, [8].

2.3 Preliminaries and useful lemmas

Now, let us assume that w is a solution of (1.8) for some initial data $w_T \in H_0^1(\Omega)$, and define

$$z(t,x) = e^{-s\sigma(t,x)} w(t,x), \tag{2.13}$$

which obviously satisfies

$$z(T) = z(0) = 0 \qquad \text{in } H_0^1(\Omega) \tag{2.14}$$

due to the assumptions (2.3) on σ. The positive parameter s in (2.13) is aimed to be large. Then, plugging $w = z\exp(\sigma(t,x))$ in the equation (1.8), we obtain that z satisfies

$$\partial_t z + \Delta z + \frac{\mu}{|x|^2} z + 2s\nabla z \cdot \nabla\sigma + sz\Delta\sigma + z\Big(s\partial_t\sigma + s^2|\nabla\sigma|^2\Big) = 0, \quad (x,t) \in \Omega \times (0,T), \tag{2.15}$$

with the boundary condition

$$z = 0, \quad (x,t) \in \partial\Omega \times (0,T). \tag{2.16}$$

Let us define a smooth positive radial function $\alpha(x) = \alpha(|x|)$ such that

$$\alpha(x) = \begin{cases} 0, & |x| \leq r_0/2, \\ 1/N, & |x| \geq r_0, \end{cases} \tag{2.17}$$

where $r_0 > 0$ is selected as in (2.5).

Setting

$$\begin{aligned} Sz &= \Delta z + \frac{\mu}{|x|^2} z + z\Big(s\partial_t\sigma + s^2|\nabla\sigma|^2\Big), \\ Az &= \partial_t z + 2s\nabla z \cdot \nabla\sigma + sz\Delta\sigma\Big(1+\alpha\Big), \\ Pz &= -s\alpha\Delta\sigma z \end{aligned} \tag{2.18}$$

One easily deduces from (2.15) that

$$Sz + Az + Pz = 0, \qquad ||Sz||^2 + ||Az||^2 + 2 < Sz, Az >= ||Pz||^2,$$

where $||\cdot||$ denotes the $L^2(\Omega \times (0,T))$ norm and $< \cdot, \cdot >$ the corresponding scalar product. Especially, the quantity

$$I =< Sz, Az > -\frac{1}{2}||s\alpha z\Delta\sigma||^2 \tag{2.19}$$

is non positive.

Lemma 2.3. *The following equality holds:*

$$\begin{aligned} I = -2s \iint\limits_{\Omega\times(0,T)} D^2\sigma(\nabla z, \nabla z)\ \mathrm{dx\ dt} + s \iint\limits_{\partial\Omega\times(0,T)} |\partial_n z|^2\ \partial_n\sigma\ \mathrm{ds\ dt} \\ - s \iint\limits_{\Omega\times(0,T)} |\nabla z|^2 \Delta\sigma\ \alpha\ \mathrm{dx\ dt} + \frac{s}{2} \iint\limits_{\Omega\times(0,T)} |z|^2 \Delta^2\sigma\Big(1+\alpha\Big)\ \mathrm{dx\ dt} \\ + s \iint\limits_{\Omega\times(0,T)} |z|^2 \nabla\alpha \cdot \nabla\Delta\sigma\ \mathrm{dx\ dt} + \frac{s}{2} \iint\limits_{\Omega\times(0,T)} |z|^2 \Delta\sigma\ \Delta\alpha\ \mathrm{dx\ dt} \\ - \frac{1}{2} \iint\limits_{\Omega\times(0,T)} |z|^2 \Big(s\partial_{tt}^2\sigma + 2s^2\partial_t\Big(|\nabla\sigma|^2\Big)\Big)\ \mathrm{dx\ dt} - 2s^3 \iint\limits_{\Omega\times(0,T)} |z|^2 D^2\sigma\Big(\nabla\sigma, \nabla\sigma\Big)\ \mathrm{dx\ dt} \\ + \iint\limits_{\Omega\times(0,T)} \alpha|z|^2\Delta\sigma\Big(s^2\partial_t\sigma + s^3|\nabla\sigma|^2\Big)\ \mathrm{dx\ dt} - \frac{s^2}{2} \iint\limits_{\Omega\times(0,T)} \alpha^2|z|^2|\Delta\sigma|^2\ \mathrm{dx\ dt} \\ + \mu s \iint\limits_{\Omega\times(0,T)} \frac{|z|^2}{|x|^2}\Delta\sigma\ \alpha\ \mathrm{dx\ dt} + 2\mu s \iint\limits_{\Omega\times(0,T)} \frac{|z|^2}{|x|^4} x \cdot \nabla\sigma\ \mathrm{dx\ dt} \end{aligned} \tag{2.20}$$

where $\partial_n = \vec{n} \cdot \nabla$ *and* ds *denotes the trace of the Lebesgue measure on* $\partial\Omega$.

Here we omit the proof of Lemma 2.3 since it may be found in [8]. It is worth mentioning that the upcoming computations justified by integrations by parts are done formally. However, we notice that the final estimates make sense in our functional framework. A priori the regularity of the operator $A_\mu := -\Delta - \mu/|x|^2 + \mathcal{C}_0 I$ is not enough to justify the integration by parts since the lack of regularity appears at the singular point $x = 0$. This issue is presented in a detailed manner in [5] in the context of the wave equation with singular potential localized on the boundary.

Now, we will decompose the term I in (2.20) into several terms that we handle separately.

Let us define I_{bd} the boundary term in identity (2.20):

$$I_{bd} := \iint\limits_{\partial\Omega\times(0,T)} s|\partial_n z|^2 \ \partial_n \sigma \text{ ds dt}. \tag{2.21}$$

Then define I_l as the sum of the integrals linear in σ which do not have any time derivative:

$$\begin{aligned} I_l = -2s \iint\limits_{\Omega\times(0,T)} D^2\sigma(\nabla z, \nabla z) \text{ dx dt} - s \iint\limits_{\Omega\times(0,T)} |\nabla z|^2 \Delta\sigma \ \alpha \text{ dx dt} + \frac{s}{2} \iint\limits_{\Omega\times(0,T)} |z|^2 \Delta^2\sigma\Big(1+\alpha\Big) \text{ dx dt} \\ + s \iint\limits_{\Omega\times(0,T)} |z|^2 \nabla\alpha\cdot\nabla\Delta\sigma \text{ dx dt} + \frac{s}{2} \iint\limits_{\Omega\times(0,T)} |z|^2 \Delta\sigma \ \Delta\alpha \text{ dx dt} \\ + \mu s \iint\limits_{\Omega\times(0,T)} \frac{|z|^2}{|x|^2} \Delta\sigma \ \alpha \text{ dx dt} + 2\mu s \iint\limits_{\Omega\times(0,T)} \frac{|z|^2}{|x|^4} x\cdot\nabla\sigma \text{ dx dt}. \end{aligned} \tag{2.22}$$

We then consider the integrals involving non-linear terms in σ and without any time derivative, that is

$$\begin{aligned} I_{nl} = -2s^3 \iint\limits_{\Omega\times(0,T)} |z|^2 D^2\sigma\Big(\nabla\sigma, \nabla\sigma\Big) \text{ dx dt} + s^3 \iint\limits_{\Omega\times(0,T)} \alpha|z|^2\Delta\sigma|\nabla\sigma|^2 \text{ dx dt} \\ - \frac{s^2}{2} \iint\limits_{\Omega\times(0,T)} \alpha^2|z|^2|\Delta\sigma|^2 \text{ dx}. \end{aligned} \tag{2.23}$$

We finally estimate the terms involving the time derivatives in σ:

$$I_t = -\frac{1}{2} \iint\limits_{\Omega\times(0,T)} |z|^2\Big(s\partial_{tt}^2\sigma + 2s^2\partial_t\Big(|\nabla\sigma|^2\Big)\Big) \text{ dx dt} + s^2 \iint\limits_{\Omega\times(0,T)} \alpha|z|^2\Delta\sigma\partial_t\sigma \text{ dx dt}. \tag{2.24}$$

The next step is to give convenient estimations for the terms defined above. In order to do that several lemmas are proved. Making the notations $\Omega_{r_0} = \Omega \cap B(0, r_0)$, $\mathcal{O} = \Omega \setminus (\omega_0 \cup \Omega_{r_0})$, $\tilde{\mathcal{O}} = \Omega \setminus \Omega_{r_0}$ we successively obtain

Lemma 2.4. *It holds that $I_{bd} \geq 0$, for any $\lambda > 0$.*

Lemma 2.5. *There exists λ_0 such that for any $\lambda > \lambda_0$ and any $s > 0$ then*

$$\begin{aligned} I_l \geq C_2 s \iint\limits_{\Omega\times(0,T)} \theta\Big[|x|^{2-\gamma}|\nabla z|^2 + \frac{z^2}{|x|^\gamma}\Big] \text{ dx dt} + C_7 s\lambda^2 \iint\limits_{\mathcal{O}\times(0,T)} \theta\big(\frac{|x|}{r_0}\big)^\lambda \phi|\nabla z|^2 \text{ dx dt} + \\ + C_5 s\lambda \iint\limits_{\Omega_{r_0}\times(0,T)} \theta\big(\frac{|x|}{r_0}\big)^{\lambda-2}|\nabla z|^2 \text{ dx dt} - B_\lambda s \iint\limits_{\Omega\times(0,T)} \theta|z|^2 \text{ dx dt} \\ - C_6 s\lambda^2 \iint\limits_{\omega_0\times(0,T)} \theta\big(\frac{|x|}{r_0}\big)^\lambda \phi|\nabla z|^2 \text{ dx dt}, \end{aligned} \tag{2.25}$$

where C_2, C_7, C_5, C_6 and B_λ are constants uniform in s and λ, respectively uniform in s.

Lemma 2.6. *There exists λ_0 such that for any $\lambda > \lambda_0$ there exists $s_0(\lambda)$ such that for any $s > s_0$ it holds*

$$I_{nl} \geq \frac{s^3}{2} \iint\limits_{\Omega_{r_0}\times(0,T)} \theta^3 |x|^2 |z|^2 \text{ dx dt} + C_{15} s^3 \lambda^4 \iint\limits_{\mathcal{O}\times(0,T)} \theta^3 \big(\frac{1}{r_0}\big)^{3\lambda} \phi^3 |x|^{3\lambda} |z|^2 \text{ dx dt} \\ - C_{16} s^3 \lambda^4 \iint\limits_{\omega_0\times(0,T)} \theta^3 \big(\frac{1}{r_0}\big)^{3\lambda} \phi^3 |x|^{3\lambda} |z|^2 \text{ dx dt} \quad (2.26)$$

for some constants C_{15}, C_{16} uniform in s and λ.

Taking into account the negative terms in the expression of I_l that we want to get rid of, we define

$$I_r = I_t - B_\lambda s \iint\limits_{\Omega\times(0,T)} \theta |z|^2 \text{ dx dt}. \quad (2.27)$$

Then

Lemma 2.7. *There exists λ_0 such that for any $\lambda > \lambda_0$ there exists $s_0(\lambda)$ such that for any $s > s_0$ we have*

$$|I_r| \leq \frac{C_2 s}{2} \iint\limits_{Q_T} \theta \frac{|z|^2}{|x|^\gamma} \text{ dx dt} + \frac{C_{15}}{2} s^3 \lambda^4 \iint\limits_{\tilde{\mathcal{O}}\times(0,T)} \theta^3 \big(\frac{1}{r_0}\big)^{3\lambda} \phi^3 |x|^{3\lambda} |z|^2 \text{ dx dt} + \frac{s^3}{4} \iint\limits_{Q_T} \theta^3 |x|^2 |z|^2 \text{ dx dt}. \quad (2.28)$$

Carleman inequality in the variable z

From lemmas above we obtain

Theorem 2.8. *There exists a positive constant K and λ_0 such that for $\lambda \geq \lambda_0$ there exists $s_0(\lambda)$ such that for any $s \geq s_0$ we have*

$$s\lambda^2 \iint\limits_{\mathcal{O}\times(0,T)} \theta \big(\frac{|x|}{r_0}\big)^\lambda \phi |\nabla z|^2 \text{ dx dt} + s \iint\limits_{\Omega\times(0,T)} \theta \Big[|x|^{2-\gamma} |\nabla z|^2 + \frac{z^2}{|x|^\gamma}\Big] \text{ dx dt} \\ + s^3 \iint\limits_{\Omega\times(0,T)} \theta^3 |x|^2 |z|^2 \text{ dx dt} + s^3 \lambda^4 \iint\limits_{\mathcal{O}\times(0,T)} \theta^3 \big(\frac{|x|}{r_0}\big)^{3\lambda} \phi^3 |z|^2 \text{ dx dt} \\ \leq K\Big(s\lambda^2 \iint\limits_{\omega_0\times(0,T)} \theta \big(\frac{|x|}{r_0}\big)^\lambda \phi |\nabla z|^2 \text{ dx dt} + s^3 \lambda^4 \iint\limits_{\omega_0\times(0,T)} \theta^3 |x|^{3\lambda} \phi^3 |z|^2 \text{ dx dt}\Big). \quad (2.29)$$

Undoing the variables in (4.2) we obtain the conclusion of Theorem 2.2.

3 Proofs of technical lemmas

Lemma 3.1. *Let us consider the function*

$$\tau_\phi(x) = \Big(\frac{|x|}{r_0}\Big)^\lambda e^{\lambda\psi}.$$

The Hessian matrix

$$D^2 \tau_\phi = \Big[\frac{\partial^2 \tau_\phi}{\partial x_i \partial x_j}\Big]_{i,j=1,\dots N},$$

is positive definite uniformly in $|x| \le r_0$, for any $\lambda \ge 2$. More precisely, for any $\lambda \ge 2$ and any $x \in \mathbb{R}^N$ with $|x| \le r_0$ we have

$$\langle D^2\tau_\phi \xi, \xi\rangle \ge \frac{\lambda}{2}\Big(\frac{|x|}{r_0}\Big)^{\lambda-2}\phi|\xi|^2, \quad \forall\ \xi \in \mathbb{R}^N, \tag{3.1}$$

Proof of Lemma 3.1. Firstly, we write $D^2\tau_\phi(\xi,\xi) = \phi(1/r_0)^\lambda S_\phi$ where

$$\begin{aligned} S_\phi :&= \lambda|\xi|^2|x|^{\lambda-2} + \lambda(\lambda-2)|x\cdot\xi|^2|x|^{\lambda-4} + 2\lambda^2(x\cdot\xi)(\xi\cdot\nabla\psi)|x|^{\lambda-2} + \\ &+ \lambda|x|^\lambda D^2\psi(\xi,\xi) + \lambda^2|x|^\lambda|\nabla\psi\cdot\xi|^2. \end{aligned} \tag{3.2}$$

Next we use to the inequality

$$2\lambda^2(x\cdot\xi)(\nabla\psi\cdot\xi)|x|^{\lambda-2} \le a\lambda^2|x\cdot\xi|^2|x|^{\lambda-4} + \frac{\lambda^2}{a}|x|^\lambda|\nabla\psi\cdot\xi|^2, \quad \forall \quad a>0.$$

Combining this with (3.2) we obtain

$$S_\phi \ge \lambda|\xi|^2|x|^{\lambda-2} + (\lambda^2-2\lambda-a\lambda^2)|x\cdot\xi|^2|x|^{\lambda-4} + \lambda|x|^\lambda D^2\psi(\xi,\xi) + \big(\lambda^2 - \frac{\lambda^2}{a}\big)|x|^\lambda|\nabla\psi\cdot\xi|^2.$$

Next we choose $a>0$ such that $\lambda^2 - 2\lambda - a\lambda^2 = 0$, that is $a = (\lambda-2)/\lambda$. For this value of a we remark that

$$S_\phi \ge \lambda|\xi|^2|x|^{\lambda-2} + \lambda|x|^\lambda D^2\psi(\xi,\xi) - \frac{2\lambda^2}{\lambda-2}|x|^\lambda|\nabla\psi|^2|\xi|^2, \quad \forall x, \forall\xi. \tag{3.3}$$

Then we deduce that

$$S_\phi \ge \frac{\lambda}{2}|x|^{\lambda-2}|\xi|^2 + \lambda|x|^{\lambda-2}|\xi|^2\big(\frac{1}{2} - \frac{2\lambda}{\lambda-2}|x|^2|D\psi|^2_\infty - |x|^2|D^2\psi|^2_\infty\big), \tag{3.4}$$

and finally

$$S_\phi \ge \frac{\lambda}{2}|x|^{\lambda-2}|\xi|^2$$

holds true for $\lambda \ge 2$ and for any $|x| \le r_0$. This yields the proof of Lemma 3.1. □

Proof of Lemma 2.4. It suffices to prove that $\nabla\sigma\cdot\vec{n} \ge 0$ in $\partial\Omega\times(0,T)$. Firstly we have

$$\nabla\sigma = \theta(t)\Big[-2x\psi - |x|^2\nabla\psi - \big(\frac{1}{r_0}\big)^\lambda(\lambda x|x|^{\lambda-2} + \lambda|x|^\lambda\nabla\psi)\phi\Big]. \tag{3.5}$$

Dept to the first two conditions in (2.7) we have

$$\nabla\psi\cdot\vec{n} = -|\nabla\psi|, \quad \forall\ x \in \partial\Omega.$$

In consequence we get

$$\nabla\sigma\cdot\vec{n} = \theta(t)\Big[-2x\cdot\vec{n} + |x|^2|\nabla\psi| + \lambda\big(\frac{1}{r_0}\big)^\lambda\phi|x|^{\lambda-2}(|x|^2|\nabla\psi| - x\cdot\vec{n})\Big].$$

Due to (2.8) we have

$$\nabla\sigma\cdot\vec{n} \ge \theta(t)\Big[|x|^2(|\nabla\psi| - 2C_\Omega) + \lambda\phi\big(\frac{|x|}{r_0}\big)^\lambda(|\nabla\psi| - C_\Omega)\Big]$$

which is positive since ψ satisfies the third condition in (2.7). This completes the proof of Lemma 2.4. □

Proof of Lemma 2.5. The computations here require a more careful analysis. First of all, we make the notations

$$\sigma_{x^2} = -\theta(t)\tau_{x^2}, \text{ where } \tau_{x^2} = |x|^2\psi,$$

respectively

$$\sigma_{\phi} = -\theta(t)\tau_{\phi}, \text{ where } \tau_{\phi} = \big(\frac{|x|}{r_0}\big)^{\lambda}\phi.$$

and

$$\tau = \tau_{x^2} + \tau_{\phi}.$$

Next we write some formulas for τ_{x^2} and τ_{ϕ} that we are going to use in our computations. More precisely, for all $x \in \mathbb{R}^N$ and any $i, j = 1, \ldots, N$ we have

$$\begin{aligned}\partial_{x_i}\tau_{x^2} &= 2x_i\psi + |x|^2\partial_{x_i}\psi\\ \partial^2_{x_ix_j}\tau_{x^2} &= 2\delta_{i,j}\psi + 2x_i\partial_{x_j}\psi + 2x_j\partial_{x_i}\psi + |x|^2\partial^2_{x_ix_j}\psi,\end{aligned} \tag{3.6}$$

respectively

$$\begin{aligned}\partial_{x_i}\tau_{\phi} &= \big(\frac{1}{r_0}\big)^{\lambda}\big(\lambda x_i|x|^{\lambda-2} + \lambda|x|^{\lambda}\partial_{x_i}\psi\big)\phi,\\ \partial^2_{x_ix_j}\tau_{\phi} &= \big(\frac{1}{r_0}\big)^{\lambda}\Big[\lambda\delta_{ij} + \lambda(\lambda-2)x_ix_j|x|^{\lambda-4} + \lambda^2x_j\partial_{x_i}\psi|x|^{\lambda-2} + \lambda^2x_i\partial_{x_j}\psi|x|^{\lambda-2} +\\ &\quad + \lambda|x|^{\lambda}\partial_{x_ix_j}\psi + \lambda^2|x|^{\lambda}\partial_{x_i}\psi\partial_{x_j}\psi\Big]\phi,\end{aligned} \tag{3.7}$$

Computations for I_l.

Next we split I_l in two parts as $I_l := I_l^1 + I_l^2$ where

$$\begin{aligned}I_l^1 &:= -2s\iint\limits_{\Omega\times(0,T)} D^2\sigma(\nabla z, \nabla z)\ \mathrm{dx\ dt} - s\iint\limits_{\Omega\times(0,T)} \Delta\sigma\alpha|\nabla z|^2\ \mathrm{dx\ dt} + 2\mu s\iint\limits_{\Omega\times(0,T)} \frac{|z|^2}{|x|^4}x\cdot\nabla\sigma\ \mathrm{dx\ dt},\\ I_l^2 &:= \frac{s}{2}\iint\limits_{\Omega\times(0,T)} |z|^2\Delta^2\sigma\Big(1+\alpha\Big)\ \mathrm{dx\ dt} + s\iint\limits_{\Omega\times(0,T)} |z|^2\nabla\alpha\cdot\nabla\Delta\sigma\ \mathrm{dx\ dt}+\\ &\quad + \frac{s}{2}\iint\limits_{\Omega\times(0,T)} |z|^2\Delta\sigma\ \Delta\alpha\ \mathrm{dx\ dt} + \mu s\iint\limits_{\Omega\times(0,T)} \frac{|z|^2}{|x|^2}\Delta\sigma\ \alpha\ \mathrm{dx\ dt}\end{aligned} \tag{3.8}$$

Moreover, we split I_l^1 as $I_l^1 := I^1_{l,x^2} + I^1_{l,\phi}$ where

$$I^1_{l,x^2} = -2s\iint\limits_{\Omega\times(0,T)} D^2\sigma_{x^2}(\nabla z, \nabla z)\ \mathrm{dx\ dt} - s\iint\limits_{\Omega\times(0,T)} \Delta\sigma_{x^2}\alpha|\nabla z|^2\ \mathrm{dx\ dt} + 2\mu s\iint\limits_{\Omega\times(0,T)} \frac{|z|^2}{|x|^4}x\cdot\nabla\sigma_{x^2}\ \mathrm{dx\ dt} \tag{3.9}$$

$$I^1_{l,\phi} := -2s\iint\limits_{\Omega\times(0,T)} D^2\sigma_{\phi}(\nabla z, \nabla z)\ \mathrm{dx\ dt} - s\iint\limits_{\Omega\times(0,T)} \Delta\sigma_{\phi}\alpha|\nabla z|^2\ \mathrm{dx\ dt} + 2\mu s\iint\limits_{\Omega\times(0,T)} \frac{|z|^2}{|x|^4}x\cdot\nabla\sigma_{\phi}\ \mathrm{dx\ dt}. \tag{3.10}$$

Estimates for I^1_{l,x^2}:

Using the relations (3.6) we have

$$I^1_{l,x^2} = 4s \iint\limits_{\Omega\times(0,T)} \theta\Big[|\nabla z|^2 - \mu\frac{|z|^2}{|x|^2}\Big]\psi \text{ dx dt} + 8s \iint\limits_{\Omega\times(0,T)} \theta(x\cdot\nabla z)(\nabla\psi\cdot\nabla z) \text{ dx dt}$$
$$+2s \iint\limits_{\Omega\times(0,T)} \theta|x|^2 D^2\psi(\nabla z,\nabla z) \text{ dx dt} - 2\mu s \iint\limits_{\Omega\times(0,T)} \theta\frac{|z|^2}{|x|^2}(\nabla\psi\cdot x) \text{ dx dt} - s \iint\limits_{\Omega\times(0,T)} \Delta\sigma_{x^2}\alpha|\nabla z|^2 \text{ dx dt}. \tag{3.11}$$

Next, we estimate the first term in I^1_{l,x^2} applying the Hardy inequality (1.5). We proceed as follows Firstly, fixing the time and integrating in the space variable we get the identities

$$\int_\Omega z\nabla z\cdot\nabla\psi \text{ dx} = -\frac{1}{2}\int_\Omega z^2\Delta\psi \text{ dx}, \tag{3.12}$$

$$\int_\Omega |x|^{2-\gamma} z\nabla z\cdot\nabla\psi \text{ dx} = -\frac{1}{2}\int_\Omega |x|^{2-\gamma}\Delta\psi z^2 \text{ dx} - \frac{(2-\gamma)}{2}\int_\Omega (x\cdot\nabla\psi)|x|^{-\gamma}z^2 dx \tag{3.13}$$

Secondly, we apply the Hardy inequality (1.5) setting $u := z\sqrt{\psi}$. Then, according to (3.12)-(3.13) and integrating in time we have

$$C_1 \iint\limits_{\Omega\times(0,T)} \theta\psi z^2 \text{ dx dt} + \iint\limits_{\Omega\times(0,T)} \theta\Big[|\nabla z|^2 - \mu\frac{z^2}{|x|^2}\Big]\psi \text{ dx dt}$$
$$+\frac{1}{4}\iint\limits_{\Omega\times(0,T)} \theta z^2\frac{|\nabla\psi|^2}{\psi} \text{ dx dt} - \frac{1}{2}\iint\limits_{\Omega\times(0,T)} \theta z^2\Delta\psi \text{ dx dt}$$
$$\geq C_2 \iint\limits_{\Omega\times(0,T)} \theta\Big[|x|^{2-\gamma}|\nabla z|^2 + \frac{z^2}{|x|^\gamma}\Big]\psi \text{ dx dt} + \frac{C_2}{4}\iint\limits_{\Omega\times(0,T)} \theta\frac{|\nabla\psi|^2}{\psi}z^2 \text{ dx dt}$$
$$-\frac{C_2}{2}\iint\limits_{\Omega\times(0,T)} \theta|x|^{2-\gamma}\Delta\psi z^2 \text{ dx dt} - C_2\frac{(2-\gamma)}{2}\iint\limits_{\Omega\times(0,T)} \theta(x\cdot\nabla\psi)|x|^{-\gamma}z^2 \text{ dx dt}.$$

Since r_0 satisfies (2.5) we have $C_2\psi/(2|x|^\gamma) \geq C_2(2-\gamma)|D\psi|_\infty|x|^{1-\gamma}/2$ for $|x| \leq r_0$. Then we easily obtain

$$\iint\limits_{\Omega\times(0,T)} \theta\Big[|\nabla z|^2 - \mu\frac{z^2}{|x|^2}\Big]\psi \text{ dx dt} \geq \frac{C_2}{2}\iint\limits_{\Omega\times(0,T)} \theta\Big[|x|^{2-\gamma}|\nabla z|^2 + \frac{z^2}{|x|^\gamma}\Big]\psi \text{ dx dt}$$
$$-\Big(C_1|\psi|_\infty + \frac{|D\psi|^2_\infty}{4} + \frac{1}{2}|D^2\psi|_\infty + \frac{C_2}{2}R_\Omega^{2-\gamma}|D^2\psi|_\infty +$$
$$+\frac{C_2}{2}(2-\gamma)r_0^{1-\gamma}|D\psi|_\infty\Big)\iint\limits_{\Omega\times(0,T)} \theta z^2 \text{ dx dt}. \tag{3.14}$$

Denoting $C_3 := C_1|\psi|_\infty + |D\psi|^2_\infty/4 + |D^2\psi|_\infty/2 + C_2R_\Omega^{2-\gamma}|D^2\psi|_\infty/2 + C_2(2-\gamma)r_0^{1-\gamma}|D\psi|_\infty/2$ and $C_2^{'} := C_2/2$, where $R_\Omega = \sup_{x\in\overline{\Omega}}|x|$, we get

$$\iint\limits_{\Omega\times(0,T)} \theta\Big[|\nabla z|^2 - \mu\frac{z^2}{|x|^2}\Big]\psi \text{ dx dt} \geq C_2^{'}\iint\limits_{\Omega\times(0,T)} \theta\Big[|x|^{2-\gamma}|\nabla z|^2 + \frac{|z|^2}{|x|^\gamma}\Big]\psi \text{ dx dt}$$
$$-C_3\iint\limits_{\Omega\times(0,T)} \theta|z|^2 \text{ dx dt}. \tag{3.15}$$

From (3.15) we obtain

$$
\begin{aligned}
I^1_{l,x^2} \geq 4sC_2^{'} \iint\limits_{\Omega\times(0,T)} \theta\Big[|x|^{2-\gamma}|\nabla z|^2 + \frac{z^2}{|x|^\gamma}\Big] \text{ dx dt} - 4sC_3 \iint\limits_{\Omega\times(0,T)} \theta|z|^2 \text{ dx dt}\\
- 8s|D\psi|_\infty \iint\limits_{\Omega\times(0,T)} \theta|x||\nabla z|^2 \text{ dx dt} - 2s|D^2\psi|_\infty \iint\limits_{\Omega\times(0,T)} \theta|x|^2|\nabla z|^2 \text{ dx dt}\\
- 2s|\mu||D\psi|_\infty \iint\limits_{\Omega\times(0,T)} \theta\frac{|z|^2}{|x|} \text{ dx dt} - s \iint\limits_{\Omega\times(0,T)} \Delta\sigma_{x^2}\alpha|\nabla z|^2 \text{ dx dt}. \quad (3.16)
\end{aligned}
$$

Since r_0 satisfies (2.5) we observe that $2C_2^{'}|x|^{2-\gamma} \geq 8|D\psi|_\infty|x| + 2|D^2\psi|_\infty|x|^2$ and $2C_2^{'}/|x|^\gamma > 2|\mu||D\psi|/|x|$, for all $|x| \leq r_0$. Hence, from above we easily obtain

$$
\begin{aligned}
I^1_{l,x^2} \geq 2sC_2^{'} \iint\limits_{\Omega\times(0,T)} \theta\Big[|x|^{2-\gamma}|\nabla z|^2 + \frac{z^2}{|x|^\gamma}\Big] \text{ dx dt} - C_4 s \iint\limits_{\Omega\times(0,T)} \theta|z|^2 \text{ dx dt}\\
- s \iint\limits_{\Omega\times(0,T)} \Delta\sigma_{x^2}\alpha|\nabla z|^2 \text{ dx dt} \quad (3.17)
\end{aligned}
$$

where $C_4 = 4C_3 + 2|\mu||D\psi|_\infty/r_0$.

Estimates for I^1_{l,σ_ϕ}*:*

In order to get rid of the gradient term with negative sign in (3.17) we have to estimate from below the quantity $\mathcal{T} := I^1_{l,\sigma_\phi} - s \iint\limits_{\Omega\times(0,T)} \Delta\sigma_{x^2}\alpha|\nabla z|^2 \text{ dx dt}$ that is

$$
\mathcal{T} = -2s \iint\limits_{\Omega\times(0,T)} D^2\sigma_\phi(\nabla z, \nabla z) \text{ dx dt} - s \iint\limits_{\Omega\times(0,T)} \Delta\sigma\alpha|\nabla z|^2 \text{ dx dt} + 2\mu s \iint\limits_{\Omega\times(0,T)} \frac{|z|^2}{|x|^4} x\cdot\nabla\sigma_\phi \text{ dx dt}.
$$

To do that, according to Lemma 3.1, formulas (3.6)-(3.7) and (2.5)-(2.9), we firstly observe the pointwise inequalities

$$
2D^2\tau_\phi(\nabla z, \nabla z) + \Delta\tau\alpha|\nabla z|^2 \geq C_5\lambda\big(\frac{|x|}{r_0}\big)^{\lambda-2}\phi|\nabla z|^2, \quad \forall x \in \Omega_{r_0} \quad (3.18)
$$

$$
\big|2D^2\tau_\phi(\nabla z, \nabla z) + \Delta\tau\alpha|\nabla z|^2\big| \leq C_6\lambda^2\big(\frac{|x|}{r_0}\big)^{\lambda}\phi|\nabla z|^2, \quad \forall\ x \in \omega_0. \quad (3.19)
$$

Since (2.2) is accomplish we get

$$
2D^2\tau_\phi(\nabla z, \nabla z) + \Delta\tau\alpha|\nabla z|^2 \geq C_7\lambda\big(\frac{|x|}{r_0}\big)^{\lambda}\phi|\nabla z|^2, \quad \forall\ x \in \mathcal{O}. \quad (3.20)
$$

for some positive constants C_5, C_6, C_7 depending on ψ. On the other hand, it holds that

$$
\frac{2\mu|x\cdot\nabla\tau_\phi|}{|x|^4} \leq C_8\lambda\big(\frac{|x|}{r_0}\big)^{\lambda-4}\phi, \quad \forall x \in \Omega. \quad (3.21)
$$

where $C_8 = C_8(\psi, \mu) > 0$. Therefore, it follows from above that

$$\mathcal{T} \geq C_7 s\lambda^2 \iint\limits_{\mathcal{O}\times(0,T)} \theta\big(\frac{|x|}{r_0}\big)^{\lambda}\phi|\nabla z|^2 \text{ dx dt}+ \\ + C_5 s\lambda \iint\limits_{\Omega_{r_0}\times(0,T)} \theta\big(\frac{|x|}{r_0}\big)^{\lambda-2}|\nabla z|^2 \text{ dx dt} - C_8 s\lambda \iint\limits_{\Omega\times(0,T)} \theta\big(\frac{|x|}{r_0}\big)^{\lambda-4}\phi|z|^2 \text{ dx dt} \\ - C_6 s\lambda^2 \iint\limits_{\omega_0\times(0,T)} \theta\big(\frac{|x|}{r_0}\big)^{\lambda}\phi|\nabla z|^2 \text{ dx dt} \tag{3.22}$$

Summing the terms in (3.17)-(3.22) we get

$$I_l^1 \geq C_2 s \iint\limits_{\Omega\times(0,T)} \theta\Big[|x|^{2-\gamma}|\nabla z|^2 + \frac{z^2}{|x|^{\gamma}}\Big] \text{ dx dt} + C_7 s\lambda^2 \iint\limits_{\mathcal{O}\times(0,T)} \theta\big(\frac{|x|}{r_0}\big)^{\lambda}\phi|\nabla z|^2 \text{ dx dt}+ \\ + C_5 s\lambda \iint\limits_{\Omega_{r_0}\times(0,T)} \theta\big(\frac{|x|}{r_0}\big)^{\lambda-2}|\nabla z|^2 \text{ dx dt} - C_8 s\lambda \iint\limits_{\Omega\times(0,T)} \theta\big(\frac{|x|}{r_0}\big)^{\lambda-4}\phi|z|^2 \text{ dx dt} \\ - C_4 s \iint\limits_{\Omega\times(0,T)} \theta|z|^2 \text{ dx dt} - C_6 s\lambda^2 \iint\limits_{\omega_0\times(0,T)} \theta\big(\frac{|x|}{r_0}\big)^{\lambda}\phi|\nabla z|^2 \text{ dx dt} \tag{3.23}$$

Estimates for I_l^2.

Making use of the support of α located far from origin we note that

$$|\Delta^2\tau_\phi|, \quad |\Delta\tau_\phi|, \quad |\nabla\Delta\tau_\phi|, \quad \Big|\alpha\frac{\Delta\tau_\phi}{|x|^2}\Big| \leq A_\lambda, \quad \forall\, x \in \Omega, \tag{3.24}$$

where A_λ is a big enough constant depending on λ. Then we get

$$I_l^2 \geq -A_\lambda s \iint\limits_{\Omega\times(0,T)} \theta|z|^2 \text{ dx dt} \tag{3.25}$$

Next we conclude

$$I_l \geq C_2 s \iint\limits_{\Omega\times(0,T)} \theta\Big[|x|^{2-\gamma}|\nabla z|^2 + \frac{z^2}{|x|^{\gamma}}\Big] \text{ dx dt} + C_7 s\lambda^2 \iint\limits_{\mathcal{O}\times(0,T)} \theta\big(\frac{|x|}{r_0}\big)^{\lambda}\phi|\nabla z|^2 \text{ dx dt}+ \\ + C_5 s\lambda \iint\limits_{\Omega_{r_0}\times(0,T)} \theta\big(\frac{|x|}{r_0}\big)^{\lambda-2}|\nabla z|^2 \text{ dx dt} - B_\lambda s \iint\limits_{\Omega\times(0,T)} \theta|z|^2 \text{ dx dt} \\ - C_6 s\lambda^2 \iint\limits_{\omega_0\times(0,T)} \theta\big(\frac{|x|}{r_0}\big)^{\lambda}\phi|\nabla z|^2 \text{ dx dt}, \tag{3.26}$$

where $B_\lambda = C_4 + A_\lambda + C_8\lambda \sup_{x\in\Omega}\{(|x|/r_0)^{\lambda}\phi\}$.

$\square$

Proof of Lemma 2.6. We split $I_{nl} = I_{nl,1} + I_{nl,2}$, where $I_{nl,1}$ are the integrals in I_{nl} restricted to

Ω_{r_0} and $I_{nl,2}$ are the terms in I_{nl} restricted to $\tilde{\mathcal{O}}$. We put $\sigma = -\theta\tau$. Then I_{nl} could be written as

$$I_{nl} = 2s^3 \iint\limits_{Q_T} \theta^3 |z|^2 D^2\tau(\nabla\tau, \nabla\tau)\ \mathrm{dx\ dt} - s^3 \iint\limits_{Q_T} \theta^3 |z|^2 \alpha \Delta\tau |\nabla\tau|^2\ \mathrm{dx\ dt} - \frac{s^2}{2} \iint\limits_{Q_T} \theta^2 \alpha^2 |z|^2 |\Delta\tau|^2\ \mathrm{dx\ dt}. \quad (3.27)$$

The term I_{nl} is even more difficult to deal with because of technical computations. First of all we have

$$\begin{aligned}
\partial_{x_i}\tau &= 2x_i\psi + |x|^2\partial_{x_i}\psi + \big(\frac{1}{r_0}\big)^\lambda \big(\lambda x_i |x|^{\lambda-2} + \lambda |x|^\lambda \partial_{x_i}\psi\big)\phi,\\
\partial^2_{x_i x_j}\tau &= 2\delta_{ij}\psi + 2x_i\partial_{x_j}\psi + 2x_j\partial_{x_i}\psi + |x|^2\partial^2_{x_i x_j}\psi + \big(\frac{1}{r_0}\big)^\lambda \Big[\lambda\delta_{ij} + \lambda(\lambda-2)x_i x_j |x|^{\lambda-4} +\\
&\quad + \lambda^2 x_j \partial_{x_i}\psi |x|^{\lambda-2} + \lambda^2 x_i \partial_{x_j}\psi |x|^{\lambda-2} + \lambda |x|^\lambda \partial_{x_i x_j}\psi + \lambda^2 |x|^\lambda \partial_{x_i}\psi \partial_{x_j}\psi\Big]\phi. \qquad (3.28)
\end{aligned}$$

Using the expressions in (3.28) we obtain several useful formulas:

$$\begin{aligned}
|x\cdot\nabla\tau|^2 &= |x|^2|\nabla\tau|^2 + \Big(|\nabla\psi\cdot x|^2 - |x|^2|\nabla\psi|^2\Big)\Big(|x|^2 + \lambda\big(\frac{1}{r_0}\big)^\lambda \phi |x|^\lambda\Big)^2,\\
(x\cdot\nabla\tau)(\nabla\psi\cdot\nabla\tau) &= |\nabla\tau|^2\nabla\psi\cdot x + \Big(|x|^2|\nabla\psi|^2 - |x\cdot\nabla\psi|^2\Big)\Big(1 + \lambda\big(\frac{1}{r_0}\big)^\lambda \phi |x|^{\lambda-2}\Big)\times\\
&\quad \times \Big(2\psi|x|^2 + \lambda\big(\frac{1}{r_0}\big)^\lambda \phi |x|^\lambda\Big),\\
|\nabla\psi\cdot\nabla\tau|^2 &= |\nabla\psi|^2|\nabla\tau|^2 + \Big(|x\cdot\nabla\psi|^2 - |x|^2|\nabla\psi|^2\Big)\Big(|x|^2 + \lambda\big(\frac{1}{r_0}\big)^\lambda \phi |x|^\lambda\Big)^2. \qquad (3.29)
\end{aligned}$$

Using the expressions in (3.29) we reach to the identity

$$\begin{aligned}
&2D^2\tau(\nabla\tau,\nabla\tau) - \alpha\Delta\tau|\nabla\tau|^2 =\\
&\quad = 2\psi(2-\alpha N)|\nabla\tau|^2 + 4(2-\alpha)|\nabla\tau|^2\nabla\psi\cdot x + 2|x|^2 D^2\psi(\nabla\tau,\nabla\tau) +\\
&\quad + 8(|x|^2|\nabla\psi|^2 - |\nabla\psi\cdot x|^2)\Big(1 + \lambda\big(\frac{1}{r_0}\big)^\lambda\phi|x|^{\lambda-2}\Big)\Big(2\psi|x|^2 + \lambda\big(\frac{1}{r_0}\big)^\lambda\phi|x|^\lambda\Big) -\\
&\quad - \alpha|x|^2\Delta\psi|\nabla\tau|^2 + \big(\frac{1}{r_0}\big)^\lambda\phi\Big\{\Big[\Big((2-\alpha)\lambda^2 - \lambda(2+\alpha N - 2\alpha)\Big)|x|^{\lambda-2} +\\
&\quad + 2\lambda^2(2-\alpha)|x|^{\lambda-2}\nabla\psi\cdot x + (2-\alpha)\lambda^2|x|^{\lambda+2}|\nabla\psi|^2\Big]|\nabla\tau|^2 +\\
&\quad + (2-\alpha)\lambda|x|^\lambda D^2\psi(\nabla\tau,\nabla\tau) + (|x|^2|\nabla\psi|^2 - |\nabla\psi\cdot x|^2)\times\\
&\quad \times\Big[4\lambda^3\big(\frac{1}{r_0}\big)^{2\lambda}\phi^2|x|^{3\lambda-4} + 8\lambda^2\big(\frac{1}{r_0}\big)^\lambda\phi|x|^{2\lambda-2} +\\
&\quad + 8\lambda^2\psi(1-\psi)|x|^\lambda - 2\lambda(\lambda-2)|x|^\lambda\Big]\Big\}.
\end{aligned}$$

Computations for $I_{nl,1}$.

Taking into account the properties of ψ and α and Lemma 3.1 we can obtain

$$2D^2\tau(\nabla\tau,\nabla\tau) - \alpha\Delta\tau|\nabla\tau|^2 \geq |\nabla\tau|^2 + \lambda^2\big(\frac{1}{r_0}\big)^\lambda\phi|x|^{\lambda-2}|\nabla\tau|^2, \quad \forall x \in \Omega_{r_0}. \qquad (3.30)$$

On the other hand we have

$$C_9|x|^2 \geq |\nabla\tau|^2 \geq |x|^2, \quad \forall\ x \in \Omega_{r_0},$$

for some constant $C_9 = C_9(\psi) > 0$, and therefore

$$\begin{aligned} 2D^2\tau(\nabla\tau, \nabla\tau) - \alpha\Delta\tau|\nabla\tau|^2\alpha^2 \geq |x|^2, \quad \forall\, x \in \Omega_{r_0}, \\ \alpha^2|\nabla\tau|^2 \leq C_9|x|^2, \quad \forall x \in \Omega_{r_0}. \end{aligned} \tag{3.31}$$

In particular we obtain

$$I_{nl,1} \geq \frac{s^3}{2} \iint\limits_{\Omega_{r_0}\times(0,T)} \theta^3|x|^2|z|^2 \text{ dx dt}. \tag{3.32}$$

for s large enough.

Computations for $I_{nl,2}$.

Again, according to the properties of ψ and α we observe that

$$\begin{aligned} 2D^2\tau(\nabla\tau, \nabla\tau) - \alpha\Delta\tau|\nabla\tau|^2 &\geq C_{10}\lambda^2\big(\frac{1}{r_0}\big)^{\lambda}\phi|x|^{\lambda}|\nabla\tau|^2 \\ &\geq C_{11}\lambda^4\big(\frac{1}{r_0}\big)^{3\lambda}|x|^{3\lambda}\phi^3, \quad \forall x \in \mathcal{O}, \\ \alpha^2|\Delta\tau|^2 &\leq C_{12}\lambda^4\big(\frac{1}{r_0}\big)^{2\lambda}\phi^2|x|^{2\lambda}, \quad \forall\, x \in \Omega \end{aligned} \tag{3.33}$$

$$\begin{aligned} \big|2D^2\tau(\nabla\tau, \nabla\tau) - \alpha\Delta\tau|\nabla\tau|^2\big| &\leq C_{13}\lambda^4\big(\frac{1}{r_0}\big)^{\lambda}\phi|x|^{\lambda}|\nabla\tau|^2 \\ &\leq C_{14}\lambda^4\big(\frac{1}{r_0}\big)^{3\lambda}|x|^{3\lambda}\phi^3, \quad \forall x \in \omega_0 \end{aligned} \tag{3.34}$$

for some uniform constants $C_{10}, C_{11}, C_{12}, C_{13}, C_{14}$ depending only on ψ. Then we obtain

$$\begin{aligned} I_{nl,2} \geq C_{10}s^3\lambda^4 \iint\limits_{\mathcal{O}\times(0,T)} \theta^3\big(\frac{1}{r_0}\big)^{3\lambda}\phi^3|x|^{3\lambda}|z|^2 \text{ dx dt} - C_{14}s^3\lambda^4 \iint\limits_{\omega_0\times(0,T)} \theta^3\big(\frac{1}{r_0}\big)^{3\lambda}\phi^3|x|^{3\lambda}|z|^2 \text{ dx dt} - \\ - C_{12}s^2\lambda^4 \iint\limits_{\tilde{\mathcal{O}}\times(0,T)} \theta^2\big(\frac{1}{r_0}\big)^{2\lambda}|x|^{2\lambda}\phi^2|z|^2 \text{ dx dt}. \end{aligned} \tag{3.35}$$

By summing the terms in (3.35)-(3.32) we obtain

$$\begin{aligned} I_{nl} \geq \frac{s^3}{2} \iint\limits_{\Omega_{r_0}\times(0,T)} \theta^3|x|^2|z|^2 \text{ dx dt} + C_{15}s^3\lambda^4 \iint\limits_{\mathcal{O}\times(0,T)} \theta^3\big(\frac{1}{r_0}\big)^{3\lambda}\phi^3|x|^{3\lambda}|z|^2 \text{ dx dt} \\ - C_{16}s^3\lambda^4 \iint\limits_{\omega_0\times(0,T)} \theta^3\big(\frac{1}{r_0}\big)^{3\lambda}\phi^3|x|^{3\lambda}|z|^2 \text{ dx dt} \end{aligned} \tag{3.36}$$

where $C_{15} = C_{10}/2$ and $C_{16} = C_{12} + C_{14}$.

□

Proof of Lemma 2.7. According to the expression of θ we obtain

$$|\theta'| \leq C\theta^{1+1/k}, \quad |\theta''| \leq C\theta^{1+2/k},$$

for some positive constant C. On the other hand according to the definition of σ we get

$$\begin{aligned} |\Delta\sigma| &\leq D_\lambda\theta, \quad \forall \quad x \in \Omega, \\ |\partial_t\sigma| &\leq D_\lambda\theta', \quad \forall \quad x \in \Omega, \\ \partial_t(|\nabla\sigma|^2) &\leq D_\lambda\theta\theta'|x|^2, \quad \forall \quad x \in \Omega_{r_0}, \\ \partial_t(|\nabla\sigma|^2) &\leq D_\lambda\theta\theta'|x|^{2\lambda}, \quad \forall \quad x \in \tilde{\mathcal{O}}, \end{aligned} \tag{3.37}$$

for a big enough constant $D_\lambda > 0$ depending on λ. Since α is supported far from origin we can write

$$s^2 \iint\limits_{\Omega\times(0,T)} \Big|\alpha|z|^2\Delta\sigma\partial_t\sigma\Big| \text{ dx dt} \leq \frac{4D_\lambda^2}{r_0^2}s^2 \iint\limits_{\Omega_{r_0}\times(0,T)} \theta^{2+1/k}|x|^2|z|^2 \text{ dx dt} + D_\lambda^2 s^2 \iint\limits_{\tilde{\mathcal{O}}\times(0,T)} \theta^{2+1/k}\, |z|^2 \text{ dx dt} \quad (3.38)$$

From (3.37) we also obtain

$$s^2 \iint\limits_{\Omega\times(0,T)} \Big||z|^2\partial_t(|\nabla\sigma|^2)\Big| \text{ dx dt} \leq D_\lambda s^2 \iint\limits_{\Omega_{r_0}\times(0,T)} \theta^{2+1/k}|x|^2|z|^2 \text{ dx dt} + D_\lambda s^2 \iint\limits_{\tilde{\mathcal{O}}\times(0,T)} \theta^{2+1/k}|x|^{2\lambda}|z|^2 \text{ dx dt}. \quad (3.39)$$

Now, we put

$$R := -\frac{s}{2} \iint\limits_{\Omega\times(0,T)} |z|^2\partial_{tt}\sigma \text{ dx dt} - B_\lambda s \iint\limits_{\Omega\times(0,T)} \theta|z|^2 \text{ dx dt},$$

where B_λ is elected as in Lemma 2.5.

Then, there exists $E_\lambda > 0$ such that

$$\Big|\frac{s}{2} \iint\limits_{\Omega\times(0,T)} |z|^2\partial_{tt}^2\sigma \text{ dx dt}\Big| \leq E_\lambda s \iint\limits_{\Omega\times(0,T)} \theta^{1+2/k}|z|^2 \text{ dx dt}$$

$$\Big|B_\lambda s \iint\limits_{\Omega\times(0,T)} \theta|z|^2 \text{ dx dt}\Big| \leq E_\lambda s \iint\limits_{\Omega\times(0,T)} \theta|z|^2 \text{ dx dt}. \quad (3.40)$$

Summing these bounds we obtain

$$|R| \leq 2sE_\lambda \iint\limits_{\Omega\times(0,T)} \theta^{1+2/k}|z|^2 dx. \quad (3.41)$$

In the sequel, we write

$$\iint\limits_{Q_T} \theta^{1+2/k}|z|^2 \text{ dx dt} = \iint\limits_{Q_T} \Big(\beta\theta^{1+2/k-1/q'}|x|^{\gamma/q'}|z|^{2/q'}\Big)\Big(\frac{1}{\beta}\theta^{1/q'}|x|^{-\gamma/q'}|z|^{2/q'}\Big) \text{ dx dt}.$$

Now we take

$$q = \frac{2+\gamma}{\gamma}, \quad q' = \frac{\gamma+2}{2}.$$

Note that $1/q + 1/q' = 1$ and applying the Young inequality we obtain

$$\iint\limits_{Q_T} \theta^{1+2/k}|z|^2 \text{ dx dt} \leq \beta^q \iint\limits_{Q_T} \theta^{(1+2/k-1/q')q}|x|^2|z|^2 dxdt + \frac{1}{\beta^{q'}} \iint\limits_{Q_T} \theta\frac{|z|^2}{|x|^\gamma} \text{ dx dt}$$

$$= \beta^q \iint\limits_{Q_T} \theta^3|x|^2|z|^2 \text{ dx dt} + \frac{1}{\beta^{q'}} \iint\limits_{Q_T} \theta\frac{|z|^2}{|x|^\gamma} \text{ dx dt}, \quad (3.42)$$

provided $k = 1 + 2/\gamma$. Therefore, from (3.41) and (3.42) we have

$$|R| \leq C(\lambda) s\Big(\beta^q \iint\limits_{Q_T} \theta^3 |x|^2 |z|^2 \text{ dx dt} + \frac{1}{\beta^{q'}} \iint\limits_{Q_T} \theta \frac{|z|^2}{|x|^\gamma} \text{ dx dt}\Big). \tag{3.43}$$

Consequently, from (3.38)-(3.43) follows

$$|I_r| \leq F_\lambda \Big(s^2 \iint\limits_{\Omega_{r_0}\times(0,T)} \theta^2 |x|^2 |z|^2 \text{ dx dt} + s\beta^q \iint\limits_{Q_T} \theta^3 |x|^2 |z|^2 \text{ dx dt}$$
$$+ \frac{s}{\beta^{q'}} \iint\limits_{\Omega\times(0,T)} \theta \frac{|z|^2}{|x|^\gamma} \text{ dx dt} + s^2 \iint\limits_{\tilde{\mathcal{O}}\times(0,T)} \theta^3 |x|^{3\lambda} |z|^2 \text{ dx dt}\Big), \tag{3.44}$$

for a new constant $F_\lambda > 0$.

Take β such that $F_\lambda/\beta^{q'} = C_2/2$. Then there exists some $s_0(\lambda)$ such that for $s \geq s_0(\lambda)$ we finish the proof of Lemma 2.7. □

4 Sketch of the proof of Theorem 1.2

Let us also assume $\omega \subset \Omega$ is a non-empty control region such that $\Omega \cap \overline{B_1(0)}$ is included in Ω and $\overline{B_1(0)} \cap \bar{\omega}$ is empty. This can always be done by a scaling argument. Moreover, let us also consider a non-empty open subset $\omega_0 \subset\subset \omega$.

Again, the proof is based on Carleman estimates as shown in Theorem 1.1. Before sketching the proof it is worthy to make some remarks about the technical difficulties that appear for domains Ω not satisfying the property (P) (as in the hypothesis of Theorem 1.2) when choosing the weight ψ.

If it were possible to construct a weight ψ as in Theorem 1.1, for a domain which does not satisfy the property (P), then the result of Theorem 1.1 could be generalized to any geometrical configuration of Ω in the sense that we could control our system with a distributed control in any open subset $\omega \subset \Omega$ no matter what the geometry of Ω is. Unfortunately, for a domain Ω as in the hypothesis of Theorem 1.2 we have not found any example of such ψ as in Subsection 2.1, since the distance function $d = d(x, \partial\Omega)$ mentioned in Remark 2.1 violates the condition (2.9) in this geometrical configuration.

Despite of this, for the proof of Theorem 1.2 (Ω not satisfying the property (P)) we choose the weight ψ to satisfy the same constraints as in Subsection 2.1 less the condition (2.9). In view of that, the result of Theorem 1.2 is weaker than the result provided by Theorem 1.1. Here we skip the details of the proof of Theorem 1.2 since it is straightforward from the Carleman estimates developed for Theorem 1.1, pointing out just the conclusions.

Indeed, when doing Carleman estimates, because the loss of condition (2.9), we cannot capture the energy in the annulus region

$$\omega' := \{x \in \Omega \mid r_0 < |x| < r_1\}, \tag{4.1}$$

where r_0 stands for the constant in (2.5) (r_0 is small enough since it is proportional with $1/|\nabla\psi|$) and r_1 is any fixed positive constant such that $r_1 \leq 1$. For that reason, we succeed to control our system forcing the control to act precisely in $\omega \cup \omega'$, where ω' is defined in (4.1). If $\omega_0^{'}$ is a non-empty open subset $\omega_0^{'} \subset\subset \omega'$ we obtain the following Carleman estimate:

Theorem 4.1. *There exists a positive constant* K_1 *and* λ_0 *such that for* $\lambda \geq \lambda_0$ *there exists* $s_0(\lambda)$

such that for any $s \geq s_0$ we have

$$
\begin{aligned}
& s\lambda^2 \iint\limits_{\mathcal{O}\times(0,T)} \theta\big(\frac{|x|}{r_0}\big)^{\lambda}\phi e^{-2s\sigma}|\nabla w|^2 \text{ dx dt} + s \iint\limits_{\Omega\times(0,T)} \theta e^{-2s\sigma}\Big[|x|^{2-\gamma}|\nabla w|^2 + \frac{w^2}{|x|^{\gamma}}\Big] \text{ dx dt} \\
& \qquad + s^3 \iint\limits_{\Omega\times(0,T)} \theta^3 e^{-2s\sigma}|x|^2|w|^2 \text{ dx dt} + s^3\lambda^4 \iint\limits_{\mathcal{O}\times(0,T)} \theta^3 e^{-2s\sigma}\big(\frac{|x|}{r_0}\big)^{3\lambda}\phi^3|w|^2 \text{ dx dt} \\
& \leq K\Big(s\lambda^2 \iint\limits_{\omega_0\cup\omega_0'\times(0,T)} \theta\big(\frac{|x|}{r_0}\big)^{\lambda}\phi e^{-2s\sigma}|\nabla w|^2 \text{ dx dt} + s^3\lambda^4 \iint\limits_{\omega_0\cup\omega_0'\times(0,T)} \theta^3\big(\frac{|x|}{r_0}\big)^{3\lambda}\phi^3 e^{-2s\sigma}|w|^2 \text{ dx dt}\Big).
\end{aligned}
\tag{4.2}
$$

In particular, according to the Cacciopoli's inequality, Theorem 4.1 yields the proof of Theorem 1.2.

Acknowledgements.

The author would like to thank Sylvain Ervedoza, Enrique Zuazua and Jean-Pierre Puel for useful suggestions related to this paper.

Partially supported by the Grants MTM2008-03541 and MTM2011-29306-C02-00 of the MICINN (Spain), project PI2010-04 of the Basque Government, the ERC Advanced Grant FP7-246775 NUMERIWAVES, the ESF Research Networking Program OPTPDE, the grant PN-II-ID-PCE-2011-3-0075 of CNCS-UEFISCDI Romania and a doctoral fellowship from UAM (Universidad Autonoma de Madrid).

References

[1] A. A. Balinsky, W. D. Evans, and R. T. Lewis, *Hardy's inequality and curvature*, http://arxiv.org/abs/1101.2331.

[2] P. Baras and J. A. Goldstein, *The heat equation with a singular potential*, Trans. Amer. Math. Soc. 284 (1984), no. 1, 121–139.

[3] P. Cannarsa, P. Martinez, and J. Vancostenoble, *Carleman estimates for a class of degenerate parabolic operators*, SIAM J. Control Optim. 47 (2008), no. 1, 1–19.

[4] C. Cazacu, *Schrdinger operators with boundary singularities: Hardy inequality, Pohozaev identity and controllability results*, http://arxiv.org/abs/1111.4568.

[5] C. Cazacu, *Hardy inequality and Pohozaev identity for operators with boundary singularities: some applications*, C. R. Acad. Sci. Paris, Ser. I 349 (2011), 1167–1172.

[6] C. Cazacu, *On Hardy inequalities with singularities on the boundary*, C. R. Acad. Sci. Paris, Ser. I 349 (2011), 273–277.

[7] H. L. Cycon, R. G. Froese, W. Kirsch, and B. Simon, *Schrödinger operators with application to quantum mechanics and global geometry*, Berlin (1987).

[8] S. Ervedoza, *Control and stabilization properties for a singular heat equation with an inversesquare potential*, Comm. Partial Differential Equations 33 (2008), no. 10-12, 1996–2019.

[9] M. M. Fall, *On the Hardy Poincaré inequality with boundary singularities*, Commun. Contemp. Math., to appear.

[10] M. M. Fall and R. Musina, *Hardy-Poincaré inequalities with boundary singularities*, Proc. Roy. Soc. Edinburgh, to appear.

[11] A. V. Fursikov and O. Yu. Imanuvilov, *Controllability of evolution equations*, Lecture Notes Series, vol. 34, Seoul National University Research Institute of Mathematics Global Analysis Research Center, Seoul, 1996.

[12] S. Gallot, D. Hulin, and J. Lafontaine, *Riemannian geometry*, Universitext, Springer-Verlag, Berlin, 1987.

[13] G. H. Hardy, J. E. Littlewood, and G. Pólya, *Inequalities*, Cambridge Mathematical Library, Cambridge University Press, Cambridge, 1988, Reprint of the 1952 edition.

[14] G.H. Hardy, *An inequality between integrals*, Messenger of Math. 54 (1925), 150–156.

[15] J.M. Lévy-Leblond, *Electron capture by polar molecules*, Phys. Rev. 153 (1967), no. 1, 1–4.

[16] J.-L. Lions, *Quelques méhodes de résolution des problèmes aux limites non lin ´aires*, Gauthier-Villars, Paris, 1969.

[17] J. Vancostenoble, *Lipschitz stability in inverse source problems for singular parabolic equations*, preprint 2012.

[18] J. Vancostenoble and E. Zuazua, *Null controllability for the heat equation with singular inverse-square potentials*, J. Funct. Anal. 254 (2008), no. 7, 1864–1902.

[19] *Hardy inequalities, observability, and control for the wave and Schrödinger equations with singular potentials*, SIAM J. Math. Anal. 41 (2009), no. 4, 1508–1532.

[20] J. L. Vázquez and E. Zuazua, *The Hardy inequality and the asymptotic behaviour of the heat equation with an inverse-square potential*, J. Funct. Anal. 173 (2000), no. 1, 103–153.